



Serviço	Sessão	Extensão	Largura considerada	Área	Volume
CBUQ espessura 5 cm	Pista simples	641,66 m	6,00 m	3849,96 m <sup>2</sup>	192,50 m <sup>3</sup>
	Pista alargada	76,00 m	proporcional	616,43 m <sup>2</sup>	30,82 m <sup>3</sup>
			Volume total		<b>223,32 m<sup>3</sup></b>
Base de BGS	Pista simples	641,66 m	6,34 m	4068,12 m <sup>2</sup>	569,54 m <sup>3</sup>
	Pista alargada	76,00 m	proporcional	646,44 m <sup>2</sup>	90,50 m <sup>3</sup>
			Volume total		<b>660,04 m<sup>3</sup></b>
Macadame	Pista simples	641,66 m	6,43 m	4125,87 m <sup>2</sup>	742,66 m <sup>3</sup>
	Pista alargada	76,00 m	proporcional	654,43 m <sup>2</sup>	117,80 m <sup>3</sup>
			Volume total		<b>860,46 m<sup>3</sup></b>
Brita antintrusiva espessura 3 cm	Pista simples	641,66 m	6,55 m	4202,87 m <sup>2</sup>	126,09 m <sup>3</sup>
	Pista alargada	76,00 m	proporcional	665,08 m <sup>2</sup>	19,95 m <sup>3</sup>
			Volume total		<b>146,04 m<sup>3</sup></b>

1:500

ESTACAS A CADA 20 METROS

OBRA / LOCAL <b>PAVIMENTAÇÃO DE RUAS</b> Estrada para Caravágio Km 0+00 a 0+717,66		
PROPRIETÁRIO Prefeitura Municipal de Cotiporá CNPJ: 90.898.487/0001-64	DATA 02/2022	
RESPONSÁVEL TÉCNICO Eng. Civil Cristiano Fugali CREA/RS 236549	DESENHO Cristiano	ESCALA INDICADA
PROJETO DE PAVIMENTAÇÃO		PRANCHA <b>02</b>